Building Systems -- How Off-Site Fabrication Affects On-Site Inspection

Presented by Rob Pickett
New England Regional Sales Manager











Sources of Information

Building Systems Councils of NAHB

- Log & Timber Homes Council
 - Panelized Homes Council
 - Modular Homes Council

https://www.nahb.org/consumers/home-buying/types-of-homeconstruction.aspx

Structural Building Components Association

https://www.sbcindustry.com/

https://www.sbcindustry.com/topical-library/audience/building-official

Structural Insulated Panel Association (SIPA)

https://www.sips.org/

Modular Building Institute (MBI)

https://www.modular.org



Building Systems Councils (BSC): Log & Timber, Panelized, Modular **Insulating Concrete Forms Manufacturers** Association (ICFMA)

http://icf-ma.org/

Harvest Homes, Inc.

www.harvesthomes.com

Superior Walls

https://www.superiorwalls.com/

Code Inspectors Checklist

https://www.superiorwalls.com/api/getFile/413

ESR-1662 - Superior Walls of America, Ltd.

https://www.superiorwalls.com/api/getFile/409







Types of Building Systems

Building System	Log & Timber	Trusses & Components	Panelized	Modular		
% Complete on delivery	20-40%	5-15%	15-50%	60-90%		
	Timber Frame / Post & Beam	Insulated concrete forms (ICFs)	Structural Insulated Panels (SIPs)	Component roof		
	Milled, Precut	Prefabricated trusses	Closed Panel	Folding roof		
	Milled, Random Length	Timber trusses	Mass Timber: Fimber trusses Cross-laminated Timber			
	Handcrafted	Precast Concrete				
		Open frame				







Building Systems Are...

- Fabricated off-site with more streamlined processes
- Built to comply with the residential construction codes effect at the delivery location.
- A better value -- Reduced material waste and greater labor efficiencies.
- Highly customizable based on engineered standards
- Verified by accredited third-parties modular certification, ANSI/APA standards, log grading per ICC400.
- Installed on permanent foundations.
- Financed like a site-built home on a different draw schedule.









Building Systems Councils of theNational Association of Home Builders

The NAHB Building Systems Councils (BSC) is the voice of the systems-built housing industry – dedicated to promoting the benefits of systems-built construction to consumers and builders.

Comprised of 6 different councils, the BSC represents manufacturers, builders and suppliers of log, timber frame, modular, panelized and concrete homes.

National Association of Home Builders

Building Systems Councils (BSC): Log & Timber, Panelized, Modular 1960 - Established as the *Home Manufacturers*Association

1985 - First annual conference, the Home Manufacturers Association Showcase


1987 - Became part of NAHB.


The Home Manufacturers Association renamed the *Building Systems Councils (BSC)*

2019 - The BSC's 34th annual conference, now called the Building Systems Housing Summit, held in Pittsburgh, PA.

Structural Building Components Association

- Founded in 1983
- Representing manufacturers of engineered floor, wall, and roof structural components
- Full scale testing
- Research & comparative studies









Structural Insulated Panel Association



NTA Evaluation Report: NER-1038, FRD031609-25 Reissue Date: 07/19/2019 This report is subject to appual review

8. FINDINGS

All products referenced herein are manufactured under an in-plant Quality Assurance program to ensure that the production quality mets or exceeds the requirements of the codes noted herein and the criteria as established by NTA, Inc. Furthermore, product must comply with the conditions of this report.

This report is subject to annual review.

10. IDENTIFICATION

Each eligible product shall be permanently marked to provide the following information:

- 10.1 The NTA, Inc. certification mark, shown below.
- 10.2 NTA's NER No. NER-1038 or FRD031609-25
- 10.3 The name of the report holder
- 10.4 Identifier for production facility
- 10.6 Project or batch number, date and shift of manufacture or other means of tracing product to quality documentation







 Non-profit trade association representing manufacturers, suppliers, dealer/distributors, design professionals, and builders

- Founded in 1990
- SIPA members provide recognition of code compliance through evaluation reports issued by the International Code Council Evaluation Service (ICC-ES) or NTA, Inc. SIPA members have access to the <u>SIPA-NTA Code Report</u>, a shared code listing managed by a group of SIPA member manufacturers.

1.1 Structural Insulated Panels. Wall and Roof Panels 8-

ft to 24-ft long, 4-5/8-in. to 15-in. thick.





This NER report is intended to indicate that NTA, inc. has evaluated the product described and found it to be eligible for labeling. Product not labeled as specified herein is not covered by this report. NTA, inc. makes no warranty, eligible, registrating the product covered by this report. For more information or questions regarding this report please contact NTA at 1-833-NER-HELP (833-837-461).

TA, INC. + 305 NORTH OAKLAND AVE + PO BOX 490 + NAPPANEE, INDIANA 48550

NER-1038 Certification Report 2019-07-19 Page 5 of 16 Certification NER Report Template 2019-01-10

FAX 574.773.226
MEMBE

Structural Insulated Panel Association (SIPA)

P.O. Box 39848

Fort Lauderdale, FL 33339

Why work with a building systems producer?

Well established businesses, e.g.

- Harvest Homes in 1961 in Delanson, NY
- Superior Wall in 1981 in New Holland, PA

Member of the national trade associations

Dedicated and experienced team









Decades of Combined Experience




- Expert staff provided with knowledge and training regarding current building trends, product innovations, and codes
- Estimators, designers and other team members are effectively an extension of your office
- Regional managers with industry experience
- Reliable, quality-driven workmanship
- Proven product specifications control costs & generate stable pricing
- Labor reduction/less onsite build time








What Does Experience Mean to You?





Wed., October 9, 2019, 11

Production Design

- Production derived from in-house design or outside design professionals
- Design services backed by years of work with outside engineers
- Programs in place to confirm specification of structural elements
- In-house design services completed to the extent of the package provided
 - Windows checked for egress, tempered glass requirements
 - Smoke detectors may not be shown
 - Electrical, mechanical, plumbing diagrams generally left to local professionals









Optimal Use

Building System	Log & Timber	Trusses & Components	Open Panels	Closed Panels	Modular
1&2 Family Detached	Primarily custom homes	ICF fdtns/walls	Custom homes	SIP walls, Precast concrete	From 2-box to 20
Multi-Family	Dorms, Lodges	Floor/roof trusses	Commodity	SIP/Precast tilt-up walls, CLT	Repeatability benefit
Commercial	Hotels, Retail, Offices	•	products	Precast tilt- up walls,	Ideal for hotels
Public/Other	NA	Integrate steel framing		CLT	High value







Why work with a building systems producer?

-- A Network of Representatives

- Builder/Dealers provide local contracting services
- Corporate and local marketing support – website, site signs, and more
- Professional feedback
- Building business together
- Coordination & support of an experienced team









Occupancy, Use & Type of Construction

The majority of the building systems in use today are wood-based, Residential Group R, Type V Construction.

- IBC requires automatic sprinkler system throughout
- Allowable building height up to 70' or four stories above grade plane.

Exceptions:

- Lightgage cold-formed steel framing per IRC R603
- ICF: Stay-in-place forms R608 (35' MRH or 2-stories above grade)
- Precast concrete can be integrated into any Type and Occupancy Group
- Cross-laminated Timber meets Type IV Construction.







Structural

Building System	Log & Timber	Trusses & Components	Open Panels	Closed Panels	Modular
Design Requirements	ICC400	Refer to https://www.sbcind ustry.com/technical	Light-frame construction; AWC WFCM	Per IRC R610	Specified prior to factory
Quality Assurance	Log Grading per ICC400 CLT per ANSI/APA PRG320	/design-specifying- installation https://www.sbcind ustry.com/technical /quality-control	Grade-marked structural panels, lumber, I- joists, beams	Per ANSI/APA PRS 610.1	production and subject to inplant third-party inspection

Many offer 10-year structural warranties from third-parties to assure compliance with codes and standards.







Fire Protection

Building System	Log & Timber	Trusses & Components	Open Panels	Closed Panels	Modular
Fire- Resistance	1-hour wall when minimum thickness is 6"	Refer to https://www.sbcind ustry.com/technical /fire-issues	Site-applied fire protection per code	production a	rior to factory nd subject to in- party inspection
Separation, Blocking	No concealed spaces in wall		Site-applied per code	SIPS require a thermal barrier	Site-applied fire separation per code.
Draftstopping	Often 2x T&G decking		Site-applied per code	Per mfr. details	Per mfr. details







Energy Conservation

Building System	Log & Timber	Trusses & Components	Open Panels	Closed Panels	Modular
Insulation	Integrated mass & insulation	Site-applied & Integrated (ICF)	Site-applied	production a	orior to factory nd subject to in- party inspection
Air Barrier	Treat as continuous insulation	Site-applied & Integrated (ICF)	Site-applied	Partially site-applied	Partially site-applied
Glazing	Often shipped loose	Not included	Ship loose or tacked in place	Ship loose or tacked in place	Tacked in place

All building systems require testing on site for air infiltration rate, duct leakage, etc.







Benefits to Sustainable Design & Construction


ICC 700-2012, Ch. 6 Resource Efficiency

601.2 Material usage. Structural systems are designed or construction techniques are implemented that reduce and optimize material usage.

601.4 Framing and structural plans. Detailed framing or structural plans, material summary lists and onsite cut lists for framing, structural materials, and sheathing materials are provided.

601.5 Prefabricated components.

Precut or preassembled components, or panelized or precast assemblies are utilized for a minimum of 90% for the following system or building...



Building systems provide green points due to their inherent practices – planning, control and utilization of materials, and less on-site waste.







Understanding the Scope of Work

Building System	Log & Timber	Trusses & Components	Open Panels	Closed Panels	Modular		
Foundation	In place prior to delivery	ICF option	In place prior to delivery	Precast option	In place prior to delivery		
	Building systems are produced to plan. Variance between plan and foundation must be rectified at the sill plate. Any modification effecting the building system will be carried up throughout the structure.						
Floor Deck	In place prior to delivery	Floor truss, I-joist or other engineered option	Panel option requires all bearing in place	CLT/SIP option	Girder built into floor, post on site		
Mechanical, Electrical, Plumbing	0-10% complete	Wet wall sub- assembly	0-10% complete	5-10% complete	70-90% complete		







Receiving a Delivery

Access

- Minimum 20' radius into driveway
- 20' wide
- Tractor-trailers are 8' wide x 70' long and 14' tall

Have foundation complete to top of sill plate

- Floor panels will rely on interior bearing being in place.
- Modulars have beam built into floor but need to have support columns per plan.
- Proximity to foundation
 - Crane: Set up close to backfilled foundation on firm, flat ground













Modular Delivery




















Storage & Handling

- Unloading to storage
 - logs or other components for installation later, use an all-terrain lull.
 - Prepare level spot for storage
- Protection from the elements
 - Sticker off grade and puddles
 - Solar degradation?



Structural Building Components Association



Building Systems Councils (BSC): Log & Timber, Panelized, Modular

Structural Insulated Panel Association

Delivery of Panels

- 30' radius all turns
- Min. roadbed width (>10')
- Check power lines
- Check overhead (<13')
- 30x70 crane operating area
- 15x70 staging for 2nd truck





Differentiation:

- Drop load or delivery service
- Extent of on-site support with delivery

Floor Construction

Floor Panels

- 8' wide, up to 34' long
- Joists & Rim lumber or engineered wood
- Sheathing ¾" T&G glued and nailed
- Crane-assisted, can average ± 960 sf/hour

Cross-laminated Timber

 Size limited by mode of transportation, similar to prestressed concrete decks



Building Systems Councils (BSC): Log & Timber, Panelized, Modular



Harvest Homes

Wall Panels

Size varies with producer

- Typical wall heights using precut studs
- Lengths vary due to anticipated handling limits
- Shorter lengths require more attention to seams

Delivery also varies with producer

- Stacked flat for forklift unloading
- Standing vertically with windows tacked into openings for crane pick
 Gables & exterior walls are sheathed
 Interior walls frame only, double top



plate







Roof Systems



Vary with producer...

 Precut or prebuilt timber trusses or prefabricated, engineered trusses

SIP panels

Folding or component modular roof



C&D Materials - Reduce, Recycle, Re-use

Building systems manage material waste in the factory, not on site, reducing costly waste removal, site clean up, even potential theft.









There is a different way to build.







